

**GOVERNMENT OF TELANGANA
MUSI RIVERFRONT DEVELOPMENT CORPORATION LIMITED**

NIT No.	Name of the work	Last Date & Time for Receipts of Bids	Name & Address of the Officer Cell. No.
Quotation Notice No.07/SE/MRDCL/ 2023-24 Dt.03.03.2024	Sealed Quotations for “Supply of Prestressed Vibrated Concrete of pedestals by using M40 grade concrete and 8no’s of 4mm prestressed intended PC wire including necessary supporting fixtures for fencing duly embossing the Logo / Name of MRDCL painted over the surface for Boundary stones at Musi River Boundary”.	Last Date for obtaining specification: 07-03-2024 03:00 PM Last date of receipt of sealed Quotations: 07-03-2024 04:00 PM	O/o Superintending Engineer, MRDCL, 6309062591

Note: Specification can be downloaded from the website : <https://musi.telangana.gov.in>
and sealed quotations to be submitted in the office of the Superintending Engineer
MRDCL, DCC complex, Block E, 2nd Floor, Tarnaka, Hyderabad-07.

Sd/-
Superintending Engineer,
MRDCL

Quotation

Supply of Prestressed Vibrated Concrete of pedestals by using M40 grade concrete and 8no's of 4mm prestressed intended PC wire.

S.No	Description	Unit	Qty	Rate
1.	Supply of Prestressed Vibrated Concrete pedestal of size 300x300x2000mm by using M40 grade concrete and 8no's of 4mm prestressed intended PC wire including necessary supporting fixtures for fencing duly embossing the Logo / Name of MRDCL painted over the surface for Boundary stones at Musi River Boundary including all material, Labour Charges transportation including Taxes etc.,.	Each	350	
2.	Supply of Prestressed Vibrated Concrete pedestal of size 300x300x3000mm by using M40 grade concrete and 8no's of 4mm prestressed intended PC wire including necessary supporting fixtures for fencing duly embossing the Logo / Name of MRDCL painted over the surface for Boundary stones at Musi River Boundary including all material, Labour Charges transportation including Taxes etc.,.	Each	500	
3.	Supply of Prestressed Vibrated Concrete pedestal of size 300x300x4000mm by using M40 grade concrete and 8no's of 4mm prestressed intended PC wire including necessary supporting fixtures for fencing duly embossing the Logo / Name of MRDCL painted over the surface for Boundary stones at Musi River Boundary including all material, Labour Charges transportation including Taxes etc.,.	Each	250	

**Sd/-
Superintending Engineer,
MRDCL**